



# Test Report: HLP-80H-36

---

80W Single Output Switching Power Supply

## ■ DESIGN VERIFY TEST

Output Function Test  
Input Function Test  
Protection Function Test  
Control Function Test  
Component Stress Test

## ■ SAFETY & E.M.C. TEST

Safety Test  
E.M.C. Test

## ■ RELIABILITY TEST

ENVIRONMENT TEST

## DESIGN VERIFY TEST

### OUTPUT FUNCTION TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT
1	RIPPLE & NOISE	V1 : 200 mVp-p (Max)	I/P : 230VAC O/P : FULL LOAD Ta : 25°C	V1 : 36.2 mVp-p (Max)
2	OUTPUT VOLTAGE ADJUST RANGE	CH1 : 33V ~ 40 V	I/P : 230 VAC I/P : 115 VAC O/P : MIN LOAD Ta : 25°C	31.749 V ~ 40.671 V / 230 VAC 31.753 V ~ 40.673 V / 115 VAC
3	CURRENT ADJUST RANGE	CH1 : 1.84 A ~ 2.3 A	I/P : 230 VAC I/P : 115 VAC O/P : MIN LOAD Ta : 25°C	1.347 A ~ 2.546 A / 230 VAC 1.358 A ~ 2.577 A / 115 VAC
4	OUTPUT VOLTAGE TOLERANCE	V1 : 1 %~ -1 % (Max)	I/P : 100 VAC / 305 VAC O/P : FULL/ MIN LOAD Ta : 25°C	V1 : 0.13 %~ -0.13 %
5	LINE REGULATION	V1 : 0.5 %~ -0.5 % (Max)	I/P : 100VAC ~ 305 VAC O/P : FULL LOAD Ta : 25°C	V1 : 0 %~ 0 %
6	LOAD REGULATION	V1 : 0.5%~ -0.5 % (Max)	I/P : 230 VAC O/P : FULL ~MIN LOAD Ta : 25°C	V1 : 0.07 %~ -0.07 %
7	SET UP TIME	230VAC : 500 ms (Max) 115VAC : 1200 ms(Max)	I/P : 230 VAC I/P : 115 VAC O/P : FULL LOAD Ta : 25°C	230VAC/ 271 ms 115VAC/ 272 ms
8	RISE TIME	230VAC : 200 ms (Max) 115VAC : 200 ms (Max)	I/P : 230 VAC I/P : 115 VAC O/P : FULL LOAD Ta : 25°C	230VAC/ 30 ms 115VAC/ 25 ms
9	HOLD UP TIME	230VAC : 16 ms (TYP) 115VAC : 16 ms (TYP)	I/P : 230 VAC I/P : 115 VAC O/P : FULL LOAD Ta : 25°C	230VAC/ 80 ms 115VAC/ 34 ms
10	OVER/UNDERSHOOT TEST	< ±5%	I/P : 230 VAC O/P : FULL LOAD Ta : 25°C	TEST : <5 %
11	DYNAMIC LOAD	V1 : 3600 mVp-p	I/P : 230 VAC (1).O/P : FULL /Min LOAD 90%DUTY/ 1KHZ (2).O/P : FULL /Min LOAD 50%DUTY/ 120HZ Ta : 25°C	(1)392 mVp-p (2)392 mVp-p

12	DIMMER TEST	SPEC:										
		*Reference resistance value for output current adjustment (Typical)										
		Resistance value	10K	20K	30K	40K	50K	60K	70K	80K	90K	100K
		Output current	10%	20%	30%	40%	50%	60%	70%	80%	90%	100%
		*1 ~ 10V dimming function for output current adjustment (Typical)										
		Dimming value	1V	2V	3V	4V	5V	6V	7V	8V	9V	10V
		Output current	10%	20%	30%	40%	50%	60%	70%	80%	90%	100%
		*10V PWM signal for output current adjustment (Typical)										
		Duty value	10%	20%	30%	40%	50%	60%	70%	80%	90%	100%
		Output current	10%	20%	30%	40%	50%	60%	70%	80%	90%	100%
		TEST RESULT: I/P : 230 VAC ; Ta : 25°C										
		1	Resistance value	10K	20K	30K	40K	50K	60K	70K	80K	90K
Output current	0.285A		0.484A	0.723A	0.957A	1.207A	1.420A	1.641A	1.867A	2.115A	2.339A	
%	12.39%		21.04%	31.43%	41.61%	52.48%	61.74%	71.35%	81.17%	91.96%	101.70%	
2	Dimming value	1V	2V	3V	4V	5V	6V	7V	8V	9V	10V	
	Output current	0.280A	0.501A	0.709A	0.936A	1.167A	1.397A	1.624A	1.855A	2.082A	2.309A	
	%	12.17%	21.78%	30.83%	40.70%	50.74%	60.74%	70.61%	80.65%	90.52%	100.39%	
3	Duty value	10%	20%	30%	40%	50%	60%	70%	80%	90%	100%	
	Output current	0.230A	0.463A	0.680A	0.919A	1.159A	1.398A	1.638A	1.878A	2.119A	2.357A	
	%	10.00%	20.13%	29.57%	39.96%	50.39%	60.78%	71.22%	81.65%	92.13%	102.48%	

## INPUT FUNCTION TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT
1	INPUT VOLTAGE RANGE	90VAC~305 VAC	I/P : TESTING O/P : FULL LOAD Ta : 25°C  I/P : LOW-LINE=3V= 87 V HIGH-LINE=305 V O/P : FULL/MIN LOAD ON : 30 Sec. OFF : 30 Sec 10MIN ( AC POWER ON/OFF NO DAMAGE )	70 V~305V  TEST : OK
2	INPUT FREQUENCY RANGE	47HZ ~63 HZ NO DAMAGE	I/P : 90 VAC ~ 305 VAC O/P : FULL -MIN LOAD Ta : 25°C	TEST : OK
3	POWER FACTOR	0.96 / 230 VAC(TYP) 0.96 / 115 VAC(TYP) 0.94 / 277 VAC(TYP)	I/P : 230 VAC I/P : 115 VAC I/P : 277 VAC O/P : FULL LOAD Ta : 25°C	PF= 0.964 / 230 VAC PF= 0.989 / 115 VAC PF= 0.945 / 277 VAC
4	EFFICIENCY	90 % (TYP)	I/P : 230 VAC O/P : FULL LOAD Ta : 25°C	91.49 %

5	INPUT CURRENT	277V/ 0.4 A (TYP) 230V/ 0.425 A (TYP) 115V/ 0.85 A (TYP)	I/P : 277 VAC I/P : 230 VAC I/P : 115 VAC O/P : FULL LOAD Ta : 25°C	I = 0.35 A/ 277 VAC I = 0.40 A/ 230 VAC I = 0.79 A/ 115 VAC
6	INRUSH CURRENT	230V/ 70 A (TYP) COLD START	I/P : 230 VAC O/P : FULL LOAD Ta : 25°C	I = 63 A/ 230 VAC
7	LEAKAGE CURRENT	< 0.75 mA / 277 VAC	I/P : 277 VAC O/P : Min LOAD Ta : 25°C	L-FG : 0.2 mA N-FG : 0.2 mA

### PROTECTION FUNCTION TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT
1	OVER LOAD PROTECTION	95 % ~ 108 %	I/P : 230 VAC I/P : 115 VAC O/P : TESTING Ta : 25°C	101 %/ 230 VAC 101%/ 115 VAC Constant current limiting, recovers automatically after fault condition is removed
2	OVER VOLTAGE PROTECTION	CH1 : 41 V ~ 49V	I/P : 230 VAC I/P : 115 VAC O/P : MIN LOAD Ta : 25°C	44.432 V/ 230 VAC 44.152 V/ 115 VAC Shut down o/p voltage, re-power on to recover
3	OVER TEMPERATURE PROTECTION	NO DAMAGE	I/P : 230 VAC O/P : FULL LOAD	O.T.P. Active Shut down o/p voltage, re-power on to recover
4	SHORT PROTECTION	SHORT EVERY OUTPUT 1 HOUR NO DAMAGE	I/P : 305 VAC O/P : FULL LOAD Ta : 25°C	NO DAMAGE HICCUP

**COMPONENT STRESS TEST**

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT
1	Power Transistor (D to S) or (C to E) Peak Voltage	Q1 Rated : 12A/700V	I/P : High-Line +3V = 308 V O/P : (1)Full Load Turn on (2) Output Short (3)Full load continue Ta : 25°C	(1) 616 V (2) 476 V (3) 612 V
2	Diode Peak Voltage	Q101 Rated : 20A/170V	I/P : High-Line +3V = 308 V O/P : (1)Full Load Turn on (2)Output Short (3)Full load continue Ta : 25°C	(1) 169 V (2) 133 V (3) 168 V
3	Clamp Diode Peak Voltage	D12 Rated : 2A/800V	I/P : High-Line +3V = 308 V O/P : (1) Dynamic Load 90%Duty/1KHz (2)Full load continue Ta : 25°C	(1) 576 V (2) 578 V
4	Input Capacitor Voltage	C5 Rated : 82u/450V	I/P : High-Line +3V = 308 V O/P : (1)Full Load Turn on /Off (2) Min load Turn on /Off (3)Full Load /Min load Change Ta : 25°C	(1) 418.73 V (2) 431.02 V (3) 431.05 V
5	Control IC Voltage Test	U1 Rated : 16V~38V	I/P : High-Line +3V = 308 V O/P : (1)Full Load Turn on /Off (2) Min load Turn on /Off (3)Full Load /Min load Change Ta : 25°C	(1) 21.462 V (2) 21.416 V (3) 21.409 V
6	Power Transistor (D to S) or (C to E) Peak Voltage	Q2 Rated : 10A/600V	I/P : High-Line +3V = 308 V O/P : (1)Full Load Turn on (2) Output Short (3)Full load continue Ta : 25°C	(1) 478 V (2) 448 V (3) 438 V

■ SAFETY & E.M.C. TEST

**SAFETY TEST**

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT
1	WITHSTAND VOLTAGE	I/P-O/P : 3.75 KVAC/min I/P-FG : 2 KVAC/min O/P-FG : 1.5 KVAC/min	I/P-O/P : 4 KVAC/min I/P-FG : 2.4 KVAC/min O/P-FG : 1.8 KVAC/min Ta : 25°C	I/P-O/P : 2.44 mA I/P-FG : 2.10 mA O/P-FG : 044 mA NO DAMAGE
2	ISOLATION RESISTANCE	I/P-O/P : 500VDC>100MΩ I/P-FG : 500VDC>100MΩ O/P-FG : 500VDC>100MΩ	I/P-O/P : 500 VDC I/P-FG : 500 VDC O/P-FG : 500 VDC Ta : 25°C /70%RH	I/P-O/P : 30 GΩ I/P-FG : 30 GΩ O/P-FG : 30 GΩ NO DAMAGE
3	GROUNDING CONTINUITY	FG(PE) TO CHASSIS OR TRACE < 100 mΩ	40 A / 2min Ta : 25°C / 70%RH	9 mΩ

**E.M.C TEST**

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT
1	HARMONIC	EN61000-3-2 CLASS A CLASS C	I/P: 230VAC/50HZ O/P:100/75/60% ELECTRONICLOAD O/P:100%LED LOAD Ta:25°C	PASS
2	CONDUCTION	EN55022 EN55015 CLASS B	I/P: 230 VAC (50HZ) O/P:FULL/60% LOAD Ta:25°C	PASS Test by certified Lab
3	RADIATION	EN55022 EN55015 CLASS B	I/P: 230 VAC (50HZ) O/P:FULL LOAD Ta:25°C	PASS Test by certified Lab
4	E.S.D	EN61000-4-2 INDUSTRY AIR:8KV / Contact:4KV	I/P: 230 VAC/50HZ O/P:FULL LOAD Ta:25°C	CRITERIA A
5	E.F.T	EN61000-4-4 INDUSTRY INPUT: 2KV	I/P: 230 VAC/50HZ O/P:FULL LOAD Ta:25°C	CRITERIA A
6	SURGE	IEC61000-4-5 INDUSTRY L-N :2KV L,N-PE:4KV	I/P: 230 VAC/50HZ O/P:FULL LOAD Ta:25°C	CRITERIA A

■ RELIABILITY TEST

ENVIRONMENT TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT																																																																				
1	TEMPERATURE RISE TEST	MODEL : HLP-80H-24 1. ROOM AMBIENT BURN-IN : 12 HRS I/P : 230VAC O/P : 95% LOAD Ta=24.7 °C 2. HIGH AMBIENT BURN-IN : 2 HRS I/P : 230VAC O/P : 95% LOAD Ta=51.5 °C	<table border="1"> <thead> <tr> <th>NO</th> <th>Position</th> <th>ROOM AMBIENT Ta= 24.7 °C</th> <th>HIGH AMBIENT Ta=51.5 °C</th> </tr> </thead> <tbody> <tr><td>1</td><td>LF2</td><td>48.4°C</td><td>73.1°C</td></tr> <tr><td>2</td><td>D6</td><td>65.0°C</td><td>87.0°C</td></tr> <tr><td>3</td><td>L3</td><td>57.6°C</td><td>80.4°C</td></tr> <tr><td>4</td><td>BD1</td><td>57.0°C</td><td>81.2°C</td></tr> <tr><td>5</td><td>C5</td><td>57.9°C</td><td>81.4°C</td></tr> <tr><td>6</td><td>Q1</td><td>62.6°C</td><td>87.3°C</td></tr> <tr><td>7</td><td>D12</td><td>67.4°C</td><td>91.5°C</td></tr> <tr><td>8</td><td>Q2</td><td>59.8°C</td><td>84.1°C</td></tr> <tr><td>9</td><td>T1</td><td>68.0°C</td><td>90.9°C</td></tr> <tr><td>10</td><td>C18</td><td>55.0°C</td><td>78.6°C</td></tr> <tr><td>11</td><td>RTH2</td><td>54.9°C</td><td>79.3°C</td></tr> <tr><td>12</td><td>U1</td><td>57.4°C</td><td>80.1°C</td></tr> <tr><td>13</td><td>Q101</td><td>55.5°C</td><td>80.5°C</td></tr> <tr><td>14</td><td>C152</td><td>60.7°C</td><td>84.4°C</td></tr> <tr><td>15</td><td>L100</td><td>43.0°C</td><td>66.8°C</td></tr> <tr><td>16</td><td>C106</td><td>47.1°C</td><td>70.9°C</td></tr> </tbody> </table>	NO	Position	ROOM AMBIENT Ta= 24.7 °C	HIGH AMBIENT Ta=51.5 °C	1	LF2	48.4°C	73.1°C	2	D6	65.0°C	87.0°C	3	L3	57.6°C	80.4°C	4	BD1	57.0°C	81.2°C	5	C5	57.9°C	81.4°C	6	Q1	62.6°C	87.3°C	7	D12	67.4°C	91.5°C	8	Q2	59.8°C	84.1°C	9	T1	68.0°C	90.9°C	10	C18	55.0°C	78.6°C	11	RTH2	54.9°C	79.3°C	12	U1	57.4°C	80.1°C	13	Q101	55.5°C	80.5°C	14	C152	60.7°C	84.4°C	15	L100	43.0°C	66.8°C	16	C106	47.1°C	70.9°C	
NO	Position	ROOM AMBIENT Ta= 24.7 °C	HIGH AMBIENT Ta=51.5 °C																																																																					
1	LF2	48.4°C	73.1°C																																																																					
2	D6	65.0°C	87.0°C																																																																					
3	L3	57.6°C	80.4°C																																																																					
4	BD1	57.0°C	81.2°C																																																																					
5	C5	57.9°C	81.4°C																																																																					
6	Q1	62.6°C	87.3°C																																																																					
7	D12	67.4°C	91.5°C																																																																					
8	Q2	59.8°C	84.1°C																																																																					
9	T1	68.0°C	90.9°C																																																																					
10	C18	55.0°C	78.6°C																																																																					
11	RTH2	54.9°C	79.3°C																																																																					
12	U1	57.4°C	80.1°C																																																																					
13	Q101	55.5°C	80.5°C																																																																					
14	C152	60.7°C	84.4°C																																																																					
15	L100	43.0°C	66.8°C																																																																					
16	C106	47.1°C	70.9°C																																																																					
2	LOW TEMPERATURE TURN ON TEST	TURN ON AFTER 2 HOUR	I/P : 305VAC/100VAC O/P : 95% LOAD Ta= -40°C / -25°C	TEST : OK																																																																				
3	HIGH HUMIDITY HIGH TEMPERATURE HIGH VOLTAGE TURN ON TEST	AFTER 12 HOURS IN CHAMBER ON CONTROL 50 °C NO DAMAGE	I/P : 305 VAC O/P : 95% LOAD Ta= 50 °C HUMIDITY= 95 %R.H	TEST : OK																																																																				
4	TEMPERATURE COEFFICIENT	± 0.03 %(0-50°C)	I/P : 230 VAC O/P : 95% LOAD	± 0.01 %(0-50°C)																																																																				
5	STORAGE TEMPERATURE TEST	1. Thermal shock Temperature : -45°C~ +90°C 2. Temperature change rate : 25°C / MIN 3. Dwell time low and high temperature : 30 MIN/EACH 4. Total test cycle : 5 CYCLE 5. Input/Output condition : STATIC		OK																																																																				
6	THERMAL SHOCK TEST	1. Thermal shock Temperature : -45°C~ +55°C 2. Temperature change rate : 25°C / MIN 3. Dwell time low and high temperature : 30 MIN/EACH 4. Total test cycle : 10 CYCLE 5. Input/Output condition : 230VAC/Full Load AC ON/OFF TEST turn on 58sec ; turn off 2sec		OK																																																																				



7	VIBRATION TEST	1 Carton & 1 Set (1) Waveform : Sine Wave (2) Frequency : 10-500Hz (3) Sweep Time : 12min/sweep cycle (4) Acceleration : 2G (5) Test Time : 60min in each axis (X.Y.Z) (6) Ta : 25°C	TEST : OK
8	CAPACITOR LIFE CYCLE	HLP-80H-24:SUPPOSE C106 IS THE MOST CRITICAL COMPONENT (1) I/P : 230VAC O/P : FULL LOAD Ta=25 °C LIFE TIME (2) I/P : 230VAC O/P : FULL LOAD Ta=50 °C LIFE TIME (3) I/P : 230VAC O/P : 75% LOAD Ta= 50 °C LIFE TIME (4) I/P : 230VAC O/P : 50% LOAD Ta= 50 °C LIFE TIME	(1) 636190 HRS (2) 138414 HRS (3) 168116 HRS (4) 204158 HRS
9	MTBF	MIL-HDBK-217F NOTICES2 PARTS COUNT TOTAL FAILURE RATE : 316.2 KHRS	
10	DMTBF/Accelerated Life Test	Demonstration Mean Time Between Failure(Expected Life) : 30,000 hours @ TA 50°C	

DATE	SAMPLE	TEST RESULT	TESTER	APPROVAL
2010/11/5	RD SAMPLE	PASS	SANFORD SU	VINCENT TSENG
2010/12/24	PRODUCT SAMPLE	PASS	SANFORD SU	VINCENT TSENG

2009/08/04 A50-F023